PETER & DONNA MARCINUK 112 SPILLER HILL ROAD RAYMOND, MAINE 04071 ANDREW MORRELL, PE #13285

28 STATE STREET GORHAM, MAINE 04038

ROBERT C. LIBBY JR., PLS #2190

BOOK 13528, PAGE 43 6. TAX MAP REFERENCE: MAP 15, LOT 123 C

22.32 ACRES RESIDENTIAL LOT - FAMILY OUTSALE

10. MINIMUM STANDARDS: LOT SIZE - 3 ACRES FRONTAGE - 225' SETBACKS - 40' FRONT, 20' SIDE & REAR

ON-SITE SEPTIC SYSTEM DRILLED WELL

14. ALL CONSTRUCTION AND SITE ALTERATIONS SHALL BE DONE IN ACCORDANCE WITH THE EROSION PREVENTION PROVISIONS OUTLINED IN THE MAINE EROSION CONTROL AND SEDIMENTATION CONTROL, BMP'S LATEST REVISION.

15. PLAN REFERENCES:

A. FINAL SUBDIVISION RECORDING PLAT, AMENDMENT TO SUBDIVISION PLANS: SPILLER HILL/GAY BROOK LOTS, 175 SPILLER HILL ROAD, RAYMOND, MAINE, AND RECORDED IN THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN PLAN BOOK 197, PG. 528.

SPILLER HILL ROAD, RAYMOND, MAINE, FOR LEE ADAMS, JR. DATED MARCH 3, 1997, BY DESLAURIERS & ASSOCIATES, INC. JOB NO. 15018. C. FINAL PLAN GAY BROOK LOTS, DATED JUNE 13, 1995,

B. STANDARD BOUNDARY SURVEY /LOT SPLIT ON

AND RECORDED IN THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN PLAN BOOK 195, PAGE 213. D. BOUNDARY SURVEY FOR KEVIN & MARY ANN CAYER, SPILLER HILL ROAD, RAYMOND, MAINE, DATED SEPTEMBER 1993, BY BH2M, INC. AND RECORDED IN THE CUMBERLAND

REGISTRY OF DEEDS IN PLAN BOOK 193, PAGE 300.

E. AMENDED SUBDIVISION PLAN, SPILLER HILL/GAY BROOK LOTS, FOR PETER & DONNA MARCINUK, DATED NOVEMBER 2013 WITH REVISIONS THROUGH JANUARY 27, 2014, BY BH2M, INC. AND RECORDED IN THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN PLAN BOOK 214 PAGE 33.

16. FEE INTEREST IN ACCESS RIGHT OF WAY TO REMAIN WITH PARCEL OWNED BY PETER & DONNA MARCINUK (TAX MAP 15, LOT 123C). THE ACCESS RIGHT OF WAY WILL PROVIDE ACCESS AND FRONTAGE FOR THE PROPOSED FAMILY LOT.

17. BENCHMARK: NAIL SET IN UTILITY POLE #517.2. ELEVATION 508.75 APPROX. USGS.

SUSTAINABLE SOILS INC. 18. TEST PITS: SCOT MCLAREN HARRISON

19. HOUSE AND UTILITY LOCATIONS SHOWN ON THE PROPOSED LOT ARE CONCEPTUAL ONLY AND REPRESENT ONE POTENTIAL LOCATION. THIS INFORMATION IS SHOWN ONLY TO DEMONSTATE THAT THE PROPOSED LOT CAN ACCOMODATE ALL REQUIRED IMPROVEMENTS AND MEET ALL APPLICABLE SETBACK REQUIREMENTS.

20. THE CONTRACTOR SHALL IMPLEMENT ALL EROSION CONTROL METHODS SHOWN ON THE EROSION CONTROL DETAILS PLAN (SHEET 2) AS REQUIRED TO ASSURE NO EROSION OCCURS DURING THE CONSTRUCTION OF THIS PROJECT.

21. EXISTING DRIVEWAY MEETS ALL BACKLOT DRIVEWAY STANDARDS FROM THE TOWN OF RAYMOND STREET ORDINANCE, SECTION 5.5(A) - SEE PLAN & PROFILE (SHEETS 2 & 3)

22. TREE CLEARING SUMMARY:

PER TOWN OF RAYMOND ORDINANCE, ARTICLE 9, SECTION Y (PG 85) A LOT MAY BE CLEARED UP TO 25% OF THE LOT AREA OR A TOTAL 15,000 SF, WHICHEVER IS GREATER.

THE FOLLOWING IS A SUMMARY OF THE EXISTING CLEARING AS

PROPOSED LOT SIZE = 131,005 SF

25% OF THE LOT= 32,751 SF ALLOWABLE CLEARING 23. THE TOWN RESERVES THE RIGHT TO REQUEST ADDITIONAL EROSION CONTROL DEVICES BE IMPLEMENTED DURING THE CONSTRUCTION PHASE AT THE DISCRETION OF THE TOWN ENGINEER OR ROAD INSPECTOR.

24. THE APPLICANT SHALL PROVIDE COMMMON MAINTENANCE AGREEMENTS FOR ROUTINE DRIVEWAY AND WINTER MAINTENANCE BETWEEN THE THREE LOT OWNERS WHO ACCESS THE BACK LOT DRIVEWAY. THIS SHALL BE COMPLETED PRIOR TO THE TOWN ISSUING ANY CERTIFICATE OF OCCUPANCY, OR ALLOWANCE FOR HABITATION IN THE PROPOSED HOUSE.

25. SEPTIC DESIGN: SCOTT MCLAREN, SE#346

26. WAIVERS:

27. ALL HOMES SHALL BE SERVED BY NFPA 13D FIRE SPRINKLER SYSTEMS. ALL PROPOSED DESIGNS TO ADDRESS FIRE RESCUE DEPARTMENT ACCESS OR FIRE PROTECTION SHALL BE APPROVED BY RAYMOND FIRE RESCUE

28. TOPOGRAPHY: 2' LIDAR TOPOGRAPHY FROM THE MAINE OFFICE OF GIS.

29. PARCEL IS NOT WITHIN THE 100-YEAR FLOOD ZONE PER FEMA FLOOD INSURANCE RATE MAP PANEL #230205 0010 B

30. THE PROPOSED LOT WILL BE GIFTED TO THE OWNER/APPLICANT'S FAMILY. 31. APPROVAL SHALL EXPIRE IF PROJECT DOES NOT COMMENCE WITHIN 2

YEARS AND COMPLETED WITHIN 4 YEARS.

32. ANY FURTHER LOT/DWELLING CREATION OFF VIV'S WAY WILL REQUIRE THAT VIV'S WAY BE IMPROVED TO TOWN OF RAYMOND PRIVATE ROAD

33. EMERGENCY VEHICLE ACCESS FOR THIS SUBDIVISION SHALL MEET THE REQUIREMENTS OF NFPA 1 AND TOWN STREET STANDARDS.

34. THE DESIGNATED "FIRE LANE" AREAS SHALL INCLUDE THE ENTIRE 180-DEGREE TURN-AROUND AREA AND SHALL BE MARKED WITH APPROVED RFRD SIGNS THAT READ "FIRE LANE", "NO PARKING" "VEHICLES TOWED AT OWNERS EXPENSE". THE FIRE LANE SIGNS SHALL BE LOCATED ON EACH SIDE OF THE TURN-AROUND AS APPROVED BY THE RFRD.

35. EACH RESIDENTIAL CMP METER BOX SHALL INCLUDE AN OUTSIDE SERVICE

36. E-911 STREET ADDRESS SHALL BE VISIBLE FROM BOTH APPROACH DIRECTIONS ON THE PROJECT STREET. STREET ADDRESS LETTERING SHALL BE NO LESS THAN 4" IN HEIGHT AND PREFERABLY REFLECTIVE.

37. ALL PROPOSED DESIGNS TO ADDRESS FIRE RESCUE DEPARTMENT FIRE PROTECTION ISSUES SHALL BE APPROVED BY THE RAYMOND FIRE RESCUE

38. ALL PROPOSED AND EXISTING LOTS ARE SUBJECT TO THE PROPOSED ROAD MAINTENANCE AGREEMENT.

RAYMOND

LOCATION MAP SCALE: 1" = 2 MILES

PROPERTY CURVE/LINE DATA

CURVE/LINE EASEMENT DATA

E15

162.64**'**

E12 S63°33'01"W 50.00'

E13 S26°26'59"E 50.00'

E16 S63*33'01"W 43.06'

E17 S63°33'01"W 354.22'

E18 R=125.00', L=67.63'

E20 R=125.00', L=82.88'

E19 S32°33'10"W 88.11'

E21 S70°32'33"W 14.18

E22 R=10.00', L=13.41

N26**°**26'59"W 50.00'

N32**°**33**'**10**"**E

L2 N63°33'01"E

R=582.33', L=42.03'

E2 R=523.01', L=27.82'

E4 R=75.00', L=52.30'

E6 R=175.00', L=94.68'

E7 N63°33'01"E 347.28'

E8 S34°21'00"E 87.74'

E10 N63°33'01"E 150.00'

E11 S26*26'59"E 50.00'

S34°21'00"E 50.48'


E5 N32°33'10"E 88.11'

E3 R=10.00,

2ND AMENDED SUBDIVISION PLAN HILL/GAY

ESIGNED	DATE
. Libby, Jr.	October 2022
DRAWN	SCALE
Dept.	1"=100'
HECKED	JOB. NO.
A. Morrell	22219

REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED



THIS PLAN REVIEWED AND APPROVED BY THE TOWN OF RAYMOND PLANNING BOARD.

	DATE
CHAIR	

Filed in Plan Book _____ Page ____

<u>LEGEND</u>

DESCRIPTION

UTILITY POLE

TEST PIT

TREELINE

SETBACK LINE

WELL LOCATION

EXISTING STONEWALL

EDGE OF PAVEMENT

EXISTING CONTOUR

ABOVE GROUND NOW OR FORMERLY

EDGE OF STREAM

IRON PIPE/IRON ROD FOUND

DECIDUOUS TREE w/ BLAZE

CONIFEROUS TREE w/ bLAZE

CAPPED IRON ROD (PLS #2190)

5/8" IRON ROD W/ CAP TO BE SET

SYMBOL

O IPF/IRF

CIRF-1

д **(W)**

 ∞

N/F

THIS PLAN AMENDS THE PREVIOUSLY RECORDED PLAN TITLED "AMENDED SUBDIVISION PLAN, SPILLER HILL/GAY

BROOKS LOTS, RAYMOND, MAINE, DATED NOVEMBER 2013", WITH REVISIONS THROUGH JANUARY 27, 2014, AND RECORDED IN THE CUMBERLAND COUNTRY REGISTRY OF DEEDS PLAN BOOK 214, PAGE 33.

Scale: 1'' = 100'0 50' 100'

Cumberland, ss Registry of Deeds

ATTEST: _____


THE FOLLOWING EXCEPTIONS:

1. NO SURVEYORS REPORT

I CERTIFY THAT THIS SURVEY CONFORMS TO THE MAINE BOARD OF LICENSURE

FOR PROFESSIONAL LAND SURVEYORS TECHNICAL STANDARDS OF PRACTICE FOR

A STANDARD BOUNDARY SURVEY WITH



ROBERT C. LIBBY JR.

PLS #2190

EROSION AND SEDIMENT CONTROL PLAN

THIS PLAN HAS BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION IN DEVELOPING AREAS AS CONTAINED IN THE LATEST REVISION OF TO THE 2016 MAINE EROSION AND SEDIMENT CONTROL BMP'S MANUAL FOR DESIGNERS AND ENGINEERS, AND THE LATEST REVISION TO THE 2014 MAINE EROSION AND SEDIMENT CONTROL FIELD GUIDE FOR CONTRACTORS. SEE MANUALS FOR ADDITIONAL INFORMATION AND DETAILS.

DURING CONSTRUCTION THE DEVELOPER/APPLICANT OR THEIR REPRESENTATIVES WILL BE RESPONSIBLE FOR IMPLEMENTING THE EROSION AND SEDIMENT CONTROL BMP'S AS WELL ROUTINE INSPECTIONS AND MAINTENANCE OF THE BMP'S.

- THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL STRUCTURES ARE SHOWN ON THE SITE PLAN. . ALL CONSTRUCTION INSPECTIONS SHALL BE CONDUCTED BY SOMEONE WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING STANDARDS AND PERMIT CONDITIONS. CONSTRUCTION INSPECTIONS SHALL BE PERFORMED AT LEAST
- ONCE A WEEK, AND PRIOR TO AND 24 HOURS AFTER A WET WEATHER EVENT (1 INCH OR MORE IN A 24 HOUR PERIOD). CONSTRUCTION INSPECTION AND CORRECTIVE ACTION DOCUMENTATION RECORDS SHALL BE MAINTAINED FOR A MINIMUM OF 5
- 2. THE SCOPE OF CONSTRUCTION INSPECTIONS INCLUDE THE EROSION AND SEDIMENTATION CONTROL MEASURES AS WELL AS DISTURBED AREAS, MATERIAL STORAGE AREAS, AND LOCATIONS WHERE VEHICLES ENTER AND EXIT THE SITE.
- 3. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE DONE IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL BMP'S", DEPARTMENT OF ENVIRONMENTAL PROTECTION, LATEST REVISION
- 4. THOSE AREAS UNDERGOING ACTUAL CONSTRUCTION WILL BE LEFT IN AN UNTREATED OR UNVEGETATED CONDITION FOR A MINIMUM TIME. AREAS SHALL BE PERMANENTLY STABILIZED WITHIN 7 DAYS OF INITIAL DISTURBANCE OF THE SOIL. IF THE DISTURBANCE IS WITHIN 75 FEET OF A WETLAND OR WATERBODY, THE AREA SHALL BE STABILIZED WITHIN 2 DAYS OR PRIOR TO ANY STORM EVENT, WHICHEVER COMES FIRST.
- 5. EXCAVATION AND EARTHWORK SHALL BE DONE SUCH THAT NO MORE THAN 1 ACRES OF THE SITE IS WITHOUT STABILIZATION
- 6. EXPOSED AREA SHOULD BE LIMITED TO THAT WHICH CAN BE MULCHED IN ONE DAY.
- 7. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED SUCH THAT NO MORE THAN ONE ACRE OF THE SITE IS WITHOUT EROSION
- 8. SEDIMENT BARRIERS (EROSION CONTROL MIX, STONE CHECK DAMS, STABILIZED CONSTRUCTION ENTRANCE, ETC.) SHOULD BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF THE CONTRIBUTING DRAINAGE AREA ABOVE THEM. THE CONTRACTOR SHALL MAINTAIN THE STABILIZED CONSTRUCTION ENTRANCE UNTIL ALL DISTURBED AREAS ARE STABILIZED.

9. ALL SEDIMENT BARRIERS SHOULD BE INSTALLED ALONG THE CONTOUR, WITH THE ENDS TURNED UP SLOPE.

- 10. INSTALL EROSION CONTROL MIX AT TOE OF SLOPES TO FILTER SILT FROM RUNOFF. SEE E.C. MIX DETAIL FOR PROPER INSTALLATION. EROSION CONTROL MIX WILL REMAIN IN PLACE PER NOTE #7. THE USE OF AN EROSION CONTROL MIX BERM IS PROHIBITED AT THE BASE OF SLOPES STEEPER THAN 8% OR WHERE THERE IS FLOWING WATER.
- 11. ALL ERSOION CONTROL STRUCTURES WILL BE INSPECTED, REPLACED, AND/OR REPAIRED EVERY 7 DAYS AND IMMEDIATELY BEFORE AND FOLLOWING ANY SIGNIFICANT RAINFALL (1.0 INCH OR MORE IN A 24-HOUR PERIOD) OR SNOW MELT OR WHEN NO LONGER SERVICEABLE DUE TO SEDIMENT ACCUMULATION OR DECOMPOSURE. IF AN INSPECTION DETERMINES THAT A CORRECTIVE ACTION IS REQUIRED, THE ACTION OR REPAIR SHALL BE STARTED BY THE END OF THE NEXT WORKDAY AND COMPLETED WITHIN SEVEN DAYS OR BEFORE THE NEXT STORM EVENT. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE STABILIZED BY TURF. EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS OF PERMANENT STABILIZATION. PERMANENT STABILIZATION IS 90% GRASS CATCH IN VEGETATED AREAS.
- 12. NO SLOPES, EITHER PERMANENT OR TEMPORARY, SHALL BE STEEPER THAN ONE AND ONE HALF TO ONE (1.5 TO 1). 13. IF FINAL SEEDING OF THE DISTURBED AREAS IS NOT COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST, USE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY SEEDING UNTIL
- 14. TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINAL GRADED SHALL BE COMPLETED BY AUG. 15 OR 45 DAYS PRIOR TO THE FIRST KILLING FROST (OCT. 1) TO PROTECT FROM SPRING RUNOFF PROBLEMS.
- 15. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT WILL BE RETURNED TO THE SITE AND REGRADED ONTO OPEN
- 16. REVEGETATION MEASURES WILL COMMENCE UPON COMPLETION OF CONSTRUCTION EXCEPT AS NOTED ABOVE. ALL DISTURBED AREAS NOT OTHERWISE STABILIZED WILL BE GRADED, SMOOTHED, AND PREPARED FOR FINAL SEEDING AS FOLLOWS:
- a. FOUR INCHES OF LOAM WILL BE SPREAD OVER DISTURBED AREAS AND SMOOTHED TO A UNIFORM SURFACE.
- b. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 800 POUNDS PER ACRE OR 18.4 POUNDS PER 1,000 SQUARE FEET USING 10-20-20 (N-P205-K20) OR EQUIVALENT. APPLY GROUND LIMESTONE (EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB PER 1,000 SQ. FT.).
- FOLLOWING SEED BED PREPARATION, DITCHES AND BACK SLOPES WILL BE SEEDED TO A MIXTURE OF 47% CREEPING RED FESCUE, 5% REDTOP, AND 48% TALL FESCUE. THE LAWN AREAS WILL BE SEEDED TO A PREMIUM TURF MIXTURE OF 44% KENTUCKY BLUEGRASS, 44% CREEPING RED FESCUE, AND 12% PERENNIAL RYEGRASS: SEEDING RATE IS 1.03 LBS PER 1000 SQ. FT. LAWN QUALITY SOD MAY BE SUBSTITUTED FOR SEED. SEED MIX SHALL CONTAIN 10% ANNUAL RYE GRASS.
- d. HAY MULCH AT THE RATE OF 70-90 LBS PER 1000 SQUARE FEET FOR OVER 75% COVERAGE. FOR UNPROTECTED OR WINDY AREAS, ANCHOR MULCH WITH PEG AND TWINE (1 SQ. YD./BLOCK). HYDRAULIC MULCHES MAY ALSO BE USED, APPLIED AT A RATE OF 5 LBS PER 1000 SQUARE FEET FOR PAPER MULCH OR 40 LBS PER 1000 SQUARE FEET OR AS DIRECTED BY THE MANUFACTURER. ON SLOPES GREATER THAN 3:1 EROSION CONTROL MIX MAY BE USED, SEE EROSION
- A FOR DISTURBED AREAS TO BE MAINTAINED IN POST—CONSTRUCTION AS A MEADOW BUFFER APPLY NEW FUCI AND CONSERVATION WILDLIFE MIX BY NEW ENGLAND WETLAND PLANTS, INC., OF AMHERST, MASSACHUSETTS OR APPROVED
- 14. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS ONCE THE SITE IS STABILIZED WITH 90% GRASS CATCH IN VEGETATED AREAS. TEMPORARY EROSION AND SEDIMENT CONTROL BLANKET SHALL BE USED IN ALL DITCHES
- 15. WETLANDS WILL BE PROTECTED WITH A DOUBLE ROW OF EROSION CONTROL MIX OR SILT FENCE INSTALLED AT THE EDGE OF THE WETLAND OR THE BOUNDARY OF WETLAND DISTURBANCE. ALL AREAS WITHIN 75 FEET OF A PROTECTED NATURAL RESOURCE MUST BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIERS DURING WINTER CONSTRUCTION.
- 16. ALL STORMWATER WILL BE PREVENTED FROM RUNNING ONTO STOCKPILES. SEDIMENT BARRIERS WILL BE INSTALLED DOWNGRADIENT OF ALL STOCKPILES.
- . PERMANENT POST-CONSTRUCTION BMP'S (VEGETATED SWALES, WET PONDS, ETC.) WILL NOT BE USED TO MANAGE FLOWS DURING CONSTRUCTION WITHOUT SPECIAL PROTECTION AND/OR RESTORATION.

ADDITIONAL TEMPORARY SEED MIXTURE (FOR PERIODS LESS THAN 12 MONTHS): <u>RATE</u> 40 LBS/ACRE SUMMER (5/15 - 8/15) SUDANGRASS OATS 80 LBS/ACRE LATE SUMMER/EARLY FALL PERENNIAL RYEGRASS 40 LBS/ACRE FALL (9/15 - 11/1) WINTER RYE 112 LBS/ACRE WINTER (11/1 - 4/1)MULCH W/ DORMANT SEED 80 LBS/ACRE**

ANNUAL RYEGRASS

OATS

**SEED RATE ONLY EROSION CONTROL MIX

SPRING (4/1 - 7/1)

EROSION CONTROL MIX (ECM) SHALL MEET THE REQUIREMENTS PROVIDED IN THE LATEST REVISION OF MAINE DEP'S EROSION AND SEDIMENTATION CONTROL BMP MANUAL. ECM IS ACCEPTABLE FOR USE ON SLOPES OF GREATER THAN 3:1 BUT LESS THAN 2:1.

ECM SHALL CONSIST OF WELL-GRADED ORGANIC COMPONENT 50 - 100% OF DRY WEIGHT, AND COMPRISED OF FIBROUS AND ELONGATED FRAGMENTS. ECM SHALL BE FREE FROM REFUSE, MATERIAL TOXIC TO PLANT GROWTH OR CONSTRUCTION DEBRIS. ECM SHALL BE EVENLY DISTRIBUTED AND APPLIED AT A THICKNESS OF 2" ON 3:1 SLOPES, WITH AN ADDITIONAL 1/2" PER 20' OF SLOPE FOR A MAXIMUM OF 100' IN LENGTH. SLOPES GREATER THAN 3:1, ECM SHALL BE APPLIED AT THICKNESS OF 4" OR 5" FOR SLOPES GREATER THAN 60' IN LENGTH.


80 LBS/ACRE

40 LBS/ACRE

NO SLOPES, EITHER PERMANENT OR TEMPORARY, SHALL BE STEEPER THAN ONE AND ONE HALF TO ONE (1.5:1). EROSION CONTROL MIX IS AN ACCEPTABLE STABILIZATION MEASURE FOR SLOPES UP TO 3:1, WITH LIMITS THAT ARE COVERED BY NOTES ON THIS SHEET. SLOPES BETWEEN 3:1 AND 2:1 SHALL BE STABILIZED WITH EROSION CONTROL BLANKETS, AND ALL SLOPES GREATER THAN 2:1 SHALL BE STABILIZED WITH RIPRAP. SEE SLOPE STABILIZATION DETAIL FOR ADDITIONAL INFORMATION.

EROSION CONTROL DURING CONSTRUCTION WINTER CONSTRUCTION

WINTER CONSTRUCTION PERIOD: NOVEMBER 1 THROUGH APRIL 15



- INSTALL A SOD LINING IN THE DITCH:
 A DITCH MUST BE LINED WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES: PINNING
 THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND
 UNDERLYING SOIL, WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL, AND ANCHORING SOD
 AT THE BASE OF THE DITCH WITH JUTE OR PLASTIC MESH TO PREVENT THE SOD FROM SLOUGHING DURING FLOW CONDITIONS. SEE THE PERMANENT VEGETATION BMP SECTION.
- INSTALL A STONE LINING IN THE DITCH: A DITCH MUST BE LINED WITH STONE RIPRAP BY NOVEMBER 15. A REGISTERED PROFESSIONAL ENGINEER MUST BE HIRED TO DETERMINE THE STONE SIZE AND LINING THICKNESS NEEDED TO WITHSTAND THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHIN THE DITCH. IF NECESSARY, THE CONTRACTOR WILL REGRADE THE DITCH PRIOR TO PLACING THE STONE LINING SO TO PREVENT THE STONE LINING FROM REDUCING THE DITCH'S
- 3. OVERWINTER STABILIZATION OF DISTURBED SLOPES:
 ALL STONE-COVERED SLOPES MUST BE CONSTRUCTED AND STABILIZED BY NOVEMBER 15. ALL SLOPES TO BE VEGETATED
 MUST BE SEEDED AND MULCHED BY SEPTEMBER 1. THE DEPARTMENT WILL CONSIDER ANY AREA HAVING A GRADE
 GREATER THAN 15% TO BE A SLOPE. IF A SLOPE TO BE VEGETATED IS NOT STABILIZED BY SEPTEMBER 1, THEN ONE OF
 THE FOLLOWING ACTIONS MUST BE TAKEN TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER. STABILIZE THE SOIL WITH
 TEMPORARY VEGETATION AND EROSION CONTROL MATS. BY OCTOBER 1 THE DISTURBED SLOPE MUST BE SEEDED WITH
 WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET AND THEN INSTALL EROSION CONTROL MATS OR
 ANCHORED MULCH OVER THE SEEDING. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT
 LEAST 75% OF THE SLOPE BY NOVEMBER 1, THEN THE CONTRACTOR WILL COVER THE SLOPE WITH A LAYER OF EROSION
 CONTROL MIX OR WITH STONE RIPRAP AS DESCRIBED IN THE FOLLOWING STANDARDS

CONTROL MIX OR WITH STONE RIPRAP AS DESCRIBED IN THE FOLLOWING STANDARDS.

- THE DISTURBED SLOPE MUST BE STABILIZED WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE CONTRACTOR PINNING THE SOD ONTO THE SLOPE WITH WRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE CONTRACTOR WILL NOT USE LATE SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.
- STABILIZE THE SOIL WITH EROSION CONTROL MIX: EROSION CONTROL MIX MUST BE PROPERLY INSTALLED BY NOVEMBER 15. THE CONTRACTOR WILL NOT USE EROSION CONTROL MIX TO STABILIZE SLOPES HAVING GREATER THAN 50% (2H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE. SEE THE EROSION CONTROL MIX NOTES FOR ADDITIONAL CRITERIA.
- PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE DEVELOPMENT'S OWNER WILL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY ON THE SLOPE AND
- F. OVERWINTER STABILIZATION OF DISTURBED SOILS:
 BY SEPTEMBER 15, ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15% MUST BE SEEDED AND MULCHED.

 IF THE DISTURBED AREAS ARE NOT STABILIZED BY THIS DATE, THEN ONE OF THE FOLLOWING ACTIONS MUST BE TAKEN TO
- STABILIZE THE SOIL WITH TEMPORARY VEGETATION: BY OCTOBER 1, SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. MONITOR GROWTH OF THE RYE. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR FAILS TO COVER AT LEAST 90% OF THE DISTURBED SOIL BEFORE NOVEMBER 1, THEN MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED BELOW.
- STABILIZE THE SOIL WITH SOD:
 STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES
 PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLINIG THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD
 AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL.
- BY NOVEMBER 15, MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POUNDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. IMMEDIATELY AFTER APPLYING THE MULCH, ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL. PROVIDE NETTING ON ALL SLOPES GREATER THAN 8%.
- IF AN INSPECTION DETERMINES THAT A CORRECTIVE ACTION IS REQUIRED, THE ACTION OR REPAIR SHALL BE STARTED BY THE END OF THE NEXT WORKDAY AND COMPLETED WITHIN SEVEN DAYS OR BEFORE THE NEXT STORM EVENT. MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION SEASON. ONCE A WEEK AND BEFORE AND AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR CONTINUOUS FUNCTION. FOLLOWING THE TEMPORARY AND/OR FINAL SEEDING AND MULCHING, THE CONTRACTOR SHALL, IN THE SPRING, INSPECT AND REPAIR ANY DAMAGES AND OR BARE SPOTS. AN ESTABLISHED VEGETATIVE COVER MEANS A MINIMUM OF 85 TO 90% OF AREAS VEGETATED WITH VIGOROUS GROWTH.

STABILIZATION SCHEDULE BEFORE WINTER:


ALL DISTURBED AREAS MUST BE SEEDED AND MULCHED. ALL SLOPES MUST BE STABILIZED, SEEDED AND MULCHED. . GRASS LINED DITCHES AND CHANNELS MUST BE STABILIZED WITH MULCH OR AN EROSION


IF THE SLOPE IS STABILIZED WITH AN EROSION CONTROL BLANKET AND SEEDED. ALL DISTURBED AREAS TO BE PROTECTED WITH AN ANNUAL GRASS MUST BE SEEDED AT A SEEDING

- ALL STONE LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED. SLOPES THAT ARE COVERED WITH RIPRAP MUST BE CONSTRUCTED BY THAT DATE. NOVEMBER 15 6. DURING WINTER CONSTRUCTION PERIOD ALL SNOW SHALL BE REMOVED FROM AREAS OF SEEDING AND MULCHING PRIOR TO
- AREAS WITHIN 75 FEET OF STREAMS, WETLANDS, AND OTHER PROTECTED NATURAL RESOURCES THAT ARE NOT STABILIZED WITH VEGETATION BY DEC. 1 SHALL BE MULCHED AND ANCHORED WITH NETTING. IF WORK CONTINUES IN THIS AREA DURING THE WINTER, A DOUBLE LINE OF SEDIMENT BARRIERS MUST BE USED.
- 1. <u>SPILL PREVENTION:</u> CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS
 1. ON SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER, AND APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING AND IMPLEMENTATION.
- GROUNDWATER PROTECTION: DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY, AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS.
- 3. <u>FUGITIVE SEDIMENT AND DUST:</u> ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MY NOT B USED FOR DUST CONTROL. ANY OFFSITE TRACKING OF MUD OR SEDIMENT SHALL BE VACUUMED IMMEDIATELY AND PRIOR TO THE NEXT SIGNIFICANT STORM EVENT
- 4. <u>DEBRIS AND OTHER MATERIALS:</u> LITTER, CONSTRUCTION DEBRIS, AND CHEMICALS EXPOSED TO STORMWATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
- 5. <u>TRENCH OR FOUNDATION DE-WATERING:</u> TRENCH DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES, FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER MUST BE REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, AND MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT RE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE, EQUIVALENT
- . <u>NON-STORMWATER DISCHARGES:</u> IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES. WHERE ALLOWED NON-STORMWATER DISCHARGES EXIST, THEY MUST BE IDENTIFIED AND STEPS SHOULD BE TAKEN TO ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION MEASURES FOR THE NON-STORMWATER COMPONENT(S) OF THE DISCHARGE. AUTHORIZED NON-STORMWATER DISCHARGES ARE:
- DISCHARGES FROM FIREFIGHTING ACTIVITY; FIRE HYDRANT FLUSHINGS
- VEHICLE WASHWATER IF DETERGENTS ARE NOT USED AND WASHING IS LIMITED TO THE EXTERIOR OF VEHICLES (ENGINE, UNDERCARRIAGE AND TRANSMISSION WASHING IS PROHIBITED); DUST CONTROL RUNOFF IN ACCORDANCE WITH PERMIT CONDITIONS AND APPENDIX (C)(3) OF MAINE DEP 06-096
- ROUTINE EXTERNAL BUILDING WASHDOWN, NOT INCLUDING SURFACE PAINT REMOVAL, THAT DOES NOT INVOLVE - PAVEMENT WASHWATER (WHERE SPILLS/LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED, UNLESS ALL SPILLED MATERIAL HAD BEEN REMOVED) IF DETERGENTS ARE NOT USED;
- UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE; UNCONTAMINATED GROUNDWATER OR SPRING WATER: FOUNDATION OR FOOTER DRAIN-WATER WHERE FLOWS ARE NOT CONTAMINATED;
- UNCONTAMINATED EXCAVATION DEWATERING (SEE REQUIREMENTS IN APPENDIX C(5) MAINE DEP 06-096 CHAPTER POTABLE WATER SOURCES INCLUDING WATERLINE FLUSHINGS; AND - LANDSCAPE IRRIGATION.
- <u>UNAUTHORIZED NON-STORMWATER DISCHARGES:</u> THE DEPARTMENT'S APPROVAL UNDER THIS CHAPTER DOES NOT AUTHORIZE A DISCHARGE THAT IS MIXED WITH A SOURCE OF NON STORMWATER, OTHER THAN THOSE DISCHARGES IN COMPLIANCE WITH APPENDIX C(6) MAINE DEP 06-096 CHAPTER 500. SPECIFICALLY, THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE DISCHARGES OF THE FOLLOWING:
- WASTEWATER FROM THE WASHOUT OR CLEANOUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS;


 - FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE;

 - SOAPS, SOLVENTS, OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING; AND
- TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE. 8. ADDITIONAL REQUIREMENTS: ADDITIONAL REQUIREMENTS MAY BE APPLIED ON A SITE-SPECIFIC BASIS.






SILT FENCE DETAIL




TYPICAL LOAM DETAIL




TYPICAL CULVERT SECTION AT DRIVEWAY

PLACE BARRIER ALONG RELATIVELY LEVEL CONTOUR. FCM BERM PROHIBITED AT THE BASE OF SLOPES > 8% OR WHERE THERE IS FLOWING WATER. SEE MAINE EROSION AND SEDIMENT CONTROL FIELD GUIDE FOR CONTRACTORS FOR INSTALLATION INSTRUCTIONS.

EROSION CONTROL MIX SHOULD CONTAIN A WELL GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. ECM SHOULD BE FREE OF REFUSE, PHYSICAL CONTAMINATES, AND MATERIAL TOXIC TO PLANT GROWTH.





HOUSE SITE, TYP.

INSTALLATION

- 1. INSTALL SEDIMENT BARRIERS ON YOUR SITE BEFORE DISTURBING SOILS. SEE THE "SEDIMENT BARRIERS" MEASURE FOR DETAILS ON INSTALLATION AND MAINTENANCE.
- 2. CONSTRUCT A DIVERSION DITCH TO KEEP UPSLOPE RUNOFF OUT OF WORK AREA.
- 3. MARK CLEARING LIMITS ON THE SITE TO KEEP EQUIPMENT OUT OF AREAS WITH STEEP SLOPES, CHANNELIZED FLOW, OR ADJACENT SURFACE WATERS AND WETLANDS.
- 4. PRESERVE BUFFERS BETWEEN THE WORK AREA AND ANY DOWNSTREAM SURFACE WATERS AND WETLANDS. SEE THE "BUFFERS" MEASURE FOR BUFFER PRESERVATION.
- 5. USE TEMPORARY MULCH AND RYE-SEED TO PROTECT DISTURBED SOILS OUTSIDE THE ACTIVE CONSTRUCTION AREA. SEE THE "MULCHING" MEASURE AND "VEGETATION" MEASURE FOR DETAILS AND SPECIFICATIONS FOR THESE CONTROLS.
- 6. PERMANENTLY SEED AREAS NOT TO BE PAVED WITHIN SEVEN DAYS OF COMPLETING FINAL GRADING, SEE "VEGETATION" MEASURE FOR INFORMATION ON PROPER SEEDING.



DESIGNED	DATE
A. Fagan	October 2022
DRAWN	SCALE
Dept.	As Noted
CHECKED	JOB. NO.
A. Morrell	22219

DOCUMENT WITHOUT THE EXPRESSED WRITTEN CONSENT OF BH2M INC. IS PROHIBITED